

CONSTRUCTION OF COMMUNITY CENTRE

S.No	DESCRIPTIONS OF WORK/ACTIVITIES	UNIT	QUANTITY	RATE (USD)	AMOUNT (USD)
1.1	Mobilization & Site Establishment: Mobilization of labor, transport of materials, tools, and equipment to site; setting up temporary storage, site office (if required), and ensuring availability of construction utilities	LMS	1		
1.2	Site Clearance: Clearing site of vegetation, bushes, debris, and unsuitable materials; collection, loading, transportation, and safe disposal at an approved dumping area; site leveling and preparation	M2	100		
1.3	heavy-duty timber columns -Supply and install 200 x 200 mm (8" x 8")	Pcs	14		
1.4	Wall Construction (G30 Box Profile Sheets): Supply and installation of G30 gauge box profile sheet walling fixed to a timber framework; vertical jungle poles installed in holes (400mm deep at 800mm c/c); horizontal 2"x3" timber (Mussemural) bracing at 800mm c/c; includes cutting, fixing, and alignment.	m2	91		
1.5	Roof Construction (Gauge #30 Profile Sheets): Supply and installation of roofing sheets on timber trusses (2"x3"); gable roof trusses at 1000mm spacing; 800mm spaced purlins recessed into trusses; complete with nailing, overlaps, ridge capping, and installation under technical supervision.	m2	100		
1.6	Steel Wire Mesh Installation: Supply and fixing of 8mm galvanized steel wire mesh around the lower wall perimeter (1000mm height); total perimeter coverage of 30m; includes cutting, tying, fixing, and reinforcement.	M2	36		
1.7	Floor Construction: Laying 200mm hardcore base, compacted; casting 100mm thick plain cement concrete (PCC) slab (1:4 cement-sand ratio); finishing with 50mm smooth screed; includes leveling, curing, and finishing works	M3	18		
1.8	Stone Masonry Foundation: Construction of stone masonry foundation wall (400mm width x 400mm height x 30m length); includes excavation (if required), mortar application, leveling, and structural stabilization for load-bearing support	M3	4		
1.9	Door Installation: Supply and installation of Double CGI sheet door mounted on 2"x3" timber frame; size 800mm x 2000mm; includes hinges, latches, fixing, and alignment.	No	1		
2	Visibility Branding: Design adaptation and installation of ECHO and DRC branding signage as per provided specifications; includes printing, materials, and mounting.	No	1		
2.1	Ceiling Installation: Supply and installation of decorated plywood or standard ceiling boards; includes timber supports, fixing, alignment, and finishing	M2	1		
2.2	Furniture Supply: Supply and delivery of 12 plastic chairs and 1 plastic table; includes transportation to site and placem	No	1		
2.3	TOTAL FOR THE CONSTRUCTION OF 1 COMMUNITY CENTER				\$ -
2.4	GRAND TOTAL FOR THE CONSTRUCTION OF (8) COMMUNITY CENTERS				\$ -